BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZONE

APPROVED SCHEDULE-B

Name of Work :Improvements to Roads at ward No. 07, Byatarayanapura in Kallappa, munagurappa & Hoysala layout

Sl. No	Approved Quantity	Description	Unit	Approved Rates of KRIDL		
				In Figures	Amount	In Words
1	359.40	KSRRB 300-3. Earthwork excavation and foming in embankment by manual means in ordinary soil with initial lead upto 15 m. and lift of 1.5m. (When earth is taken from bank cutting or from borrow pits) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications. (excluding watering and compaction of earth) (P.No.150, I.No.19.3 of PW,P&IWTD S.R 2012-13)	Cum	74.52	26782.00	Twenty Six Thousand Seven Hundred Eighty Two Only
2	3594.00	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (P. 158, I.No. 19.64) SR-2012-13	Sqm	3.78	13585.00	Thirteen Thousand Five Hundred Eighty Five Only
3	3594.00	KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with mechinery including cost of all labour, HOM of machineries complete as per specifications. (P. 159, I.No. 19.72) SR-2012-13	Sqm	1.89	6793.00	Six Thousand Seven Hundred Ninety Three Only
4	718.80	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 168 Item No. 20.18) SR 2012-13	Cum	1059.48	761554.00	Seven Lakhs Sixty One Thousand Five Hundred Fifty Four Only
5	3594.00	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 172, Item No. 21.6) SR 2012-13	Sqm	39.64	142452.00	One Lakhs Forty two Thousand Four Hundred Fifty two Only
6	89.85	KSRRB M500-18. Providing and laying semi dense bituminous concrete25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 175, Item No. 21.20.5) SR 2012-13	Cum	8992.08	807938.00	Eight lakhs Seven Thousand Nine Hundred Thirty Eight Only

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

	120.71	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3	Cum	58.32	7040.00	Seven Thousand Forty Only
8	1448.55	Removing BS Slab of drain and stacking.	Sqm	44.47	64423.00	Sixty Four Thousand Four Hundred Twenty Three Only
9	1303.70	Refixing stone slabs of drains and pointing in CM 1:3.	Sqm	63.00	82128.00	Eighty Two Thousand One Hundred Twenty Eight Only
10	144.86	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	Sqm	315.36	45681.00	Forty Five Thousand Six Hundred Eighty one Only
11	480.11	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	Cum	81.00	38889.00	Thirty Eight Thousand Eight Hundred Eighty Nine Only

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92